



ACCESS CONTROL DOOR INFORMATION

- Door 27 – Entry G139 –(Keypads, Bglass, Reed, Auto Door)
- Door 28 – Ex Dining G171 (Keypads, Bglass, Reeds, Double Mag)
- Door 29 – C'door D153 (Keypads, Bglass, Reeds, Strike)
- Door 30 – Staff Entry G144 (Keypad, Bglass, Reed, Double Mag)
- Door 31 – Exit to St Francis (Keypads, Bglass, Reed, Strike)
- Door 32 – C'door G156 entry (Keypads, Bglass, Reed, Strike)
- Door 33 – Disabled ramp exit (Keypads, Bglass, Reed, Single Mag)
- Door 34 – Kitchen Exit (Keypads, Bglass, Reed, Strike)
- Door 35 – Kitchen Entry(Keypads, Bglass, Reed, Double Mag)

CABLE LOOM INFORMATION

- Break Glass – 4 core security cable 14/020
- Keypads – 8 Core screened data 14/020
- Electric locks – Figure 8 26/030
- Reed switches – 4 core security cable 14/020



Project:
ASSISI CENTRE

Security Locations as installed Stage 3

Drawing : CT –PACS-4

Date : 12/6/14	Approved :	Issue : 1
Drawn :DS	Scale : NTS	